

PROJECT COMPONENTS OF BURA IRRIGATION DEVELOPMENT PROJECT

PHASE 1	PHASE 2	PHASE 3
<p><i>Sheet Piling and Associated works</i> <i>i.e.:</i></p> <ul style="list-style-type: none">• Construction of a submerged weir• Excavation of diversion canal from Tana River for a length of about 100m• Construction of a head regulator• Construction of 658m long silting basin	<p><i>Completion of new main canal, its hydraulic structures and associated civil works i.e.:</i></p> <ul style="list-style-type: none">• Construction of new gravity canal• Dyke formations• Construction of service roads• Concrete lining of new gravity canal• Canal drop structures• Rehabilitation of existing main canal	<p><i>Rehabilitation of existing irrigation infrastructure i.e.:</i></p> <ul style="list-style-type: none">• Bura Command• Chewele Command• Pumwani Command• Masabubu Branch Canal